

Datum:

2008-06-20

Beskrivning standardmaskin:

Option

Längd	8000 mm
Bredd	1300 mm
Höjd	1800 mm
Höjd regelmagasin	850 mm
Höjd medbrädsmagasin	950 mm
Kapacitet	5-6 medar/min
Medlängd	400-3000 mm
Brädtjocklek	15-28
Brädbredd	50-110 mm
Antal kloss	2-10 st
Klossämneslängd	...5500 mm
Klosstjocklek	63-100 mm
Klossbredd	50-100 mm
Klosslängd	75-150 mm
Olika klosslängder i samma med	ingår
Spikdimension	45-90 mm
Antal spik-pistoler	2

Enbart klosskapning med nedräkning	ingår
Bandmatning av kloss	ingår
Manuell inmatning av spånkloss	ingår
Backspegel	ingår
Skydd vid spikpistoler	ingår
Skydd vid klossämnena	ingår
Centraldämpning av pistoler	ingår
Centrering av kloss	ingår
Indragen kloss	ingår
Spånutsug	ingår
Stängning av fotocell vid utmatning	ingår
Justerbart stöd vid klossinmatning	ingår
El-installation i fabrik	ingår
Programvara M345 plc	ingår
Verktygssats	ingår

Tillägg för modem inkl programvara och arbete

20 300

Tillägg för extra spikpistol

9 800

Specifikation Block cutter & Leg making machinery

LB Plus 3000

Date: 2011-09-28

Denomination of standard machine:

Option

1	Lenght	8000 mm
2	Widht	1300 mm
3	Height	1800 mm
4	Height magasin of blockwood	850 mm
5	Height legboards	950 mm
6	Capacity	5-6 legs/min
7	Lenght of legs	400-3000 mm
8	Thickness of boards	15-28
9	Widht of boards	50-110 mm
10	Number of blocks	2-10 pcs
11	Max length of blockwood material	...5500 mm
12	Height of blocks	63-100 mm
13	Widht of blocks	50-100 mm
14	Lenght of blocks	75-150 mm
15	Various lenght on blocks in same leg	included
16	Naildimension	45-90 mm
17	Number of nailer	2
18	Only blockcutting with countdown	Included
19	Manual beltfeeding of blocks	included
20	Manual feeding of chipboard block	included
21	Rearmirrorl	included
22	Protection around nailers	included
23	Protection infeed of block material	included
24	Silenced nailer	included
25	Centering of blocks	included
26	Wing positioned block	included
27	Hose for connection waste extractor	included
28	De-activation of sensor out-feed legs	included
29	Adjustable in-feed rail manual feeding blocks	included
30	Electrical installation	Included
31	PLC Program M345	included
	Toolkit applied	included

Additional for modem incl. Program and labour

€ 1500

Additional for extra nailer

€ 1165